

Turnkey Ice Rink Refrigeration

Client: Rankin Inlet Arena








Year: 2018

Solution: Turnkey supply of a complete ice rink refrigeration system and rink floor piping for the new Rankin Inlet Arena

Features:

- Skid mounted ammonia based chiller with three circuits (one standby)
- Heat reclaim package and dry fluid cooler
- Two Glycol make up packages
- Snow melt heat exchanger
- Ice rink floor piping
- Installation, start-up and commissioning

Highlights:

-  Custom Engineered
-  Ammonia
-  Installation
-  Skid Mounted
-  Sheet Installation
-  Start-up
-  Commissioning

Turnkey supply of a complete ice rink refrigeration system and rink floor piping for a new arena. Scope of supply included one skid mounted ammonia based chiller with three circuits (one standby), one heat reclaim package, one dry fluid cooler, two Glycol make up packages, snow melt heat exchanger, ice rink floor piping, installation, start-up and commissioning. (General contractor: Mosher Engineering)